

DESIGN CRITERIA:	
PROJECT NAME:	NORTEX STOCK 1430 J SERIES
BUILDING SQUARE FOOTAGE:	413 SF
2002 NEC	
2003 IBC	
2003 IMC	
2003 IPC	
2000 IECC W/ 2001 SUPPLEMENT	
1994 TAS	
USE GROUP:	B
CONSTRUCTION TYPE:	IBC: V-B
OCCUPANT LOAD:	5
PERMISSIBLE GAS TYPE:	<input type="checkbox"/> LP <input type="checkbox"/> NATURAL <input checked="" type="checkbox"/> N/A

DESIGN LOADS:	
ROOF LIVE LOAD:	30 PFS
FLOOR LIVE LOAD:	100 PFS (SEE S-101 FOR PEIR SPACING 50PSF)
CONC. FLOOR LIVE LOAD:	2000 LBS
WIND LOAD:	(130 MPH 3-SEC GUST)
EXPOSURE:	B
SEISMIC DESIGN CATEGORY:	1-D

SPECIAL CONDITIONS AND/OR LIMITATIONS:	
1. HANDICAP ACCESS TO BE PROVIDED AS REQUIRED BY OTHERS.	
2. THE BUILDING IS TO BE LOCATED PER THE REQUIREMENTS OF TABLE 602 OF THE 2003 IBC.	
3. ANY REQUIRED ALARM SYSTEM WILL BE INSTALLED ONSITE BY OTHERS.	

FOUNDATION NOTES:	
1. TIE DOWN ANCHORING SEE SHEET S-101	
2. CRAWL SPACE VENTILATION TO BE PROVIDED BY SITE INSTALLER PER 1203.3.1 OF 2003 IBC.	

SCOPE OF WORK:	
NOT INCLUDED IN SCOPE OF WORK	
1. UTILITIES AND UTILITY CONNECTIONS	
2. POURED CONCRETE (DRIVEWAY, SIDEWALK, SLABS, FOOTINGS, ECT.)	
3. SITE PREPARATION	
4. TAX OF ANY KIND	
5. BUILDING PERMITS	
SITE WORK	
1. NO PROVISION FOR SITE WORK HAS BEEN INCLUDED. IT IS PRESUMED THE SITE WILL PROVIDE CLEAR ACCESS FOR TRUCKS AND MODULARS.	
ADEQUATE DRAINAGE TO BE PROVIDED.	
2. ALL ELECTRICAL, PLUMBING, SEWER, & GAS SERVICE CONNECTIONS	
AND ALL CONCRETE WORK ONSITE, TO INCLUDE POURED FOOTINGS, SLABS, FOUNDATIONS, SIDEWALKS, DRIVEWAYS OF WHATEVER KIND ARE THE RESONSIBILITY OF OTHERS.	

IDENTIFICATION:	
STATE DECAL: TEXAS ENGINEER ONLY, DATA PLATE PLACED IN PANEL BOX.	
DECAL: NORTEX	

FRAME / CHASSIS:	
OUTRIGGERS:	48" O.C.
CROSSMEMBERS:	48" O.C.
BEAM:	12" JR. I-BEAM
HITCH:	DETACHABLE HITCH
AXLES:	THREE TOTAL, (2)BRAKE (1) DRAG
TIRES:	L (10-PLY)
FRAME:	HEAVY

FLOOR:	
BOTTOM BOARD:	ROLL, POLYETHYLENE FIBER MESH
INSULATION:	R-19 FACED
JOIST:	2X8 #2SYP OR BETTER AT 16" O.C.
SIDEBAND JOIST (RIM):	2X8 #2SYP OR BETTER
DECKING:	3/4" T&G OSB (DRY GUARD), GLUED, WITH SCREW ATTACHMENT
UNDERLAYMENT:	1/4" HARDIE PANEL., SCREW ATTACHMENT
COVERING:	1/8" TILE WHITE #51899; OFFICES 26OZ CARPET=SAND PEBBLES
BASE COVE:	4" RUBBER. COLOR= GREY

EXTERIOR WALLS:	
SIDEWALL HIEGHT: FULL HIEGHT REFERENCE SHEET A-301	
STUDS: 2X4 #2SYP 16"O.C. DOUBLE WHERE HEIGHT EXCEEDS 119.65"	
BOTTOM PLATE: SINGLE 2X4 #3SYP	
TOP PLATES: DOUBLE 2X4 #3SYP	
HEADERS: DOUBLE 2X6 W/ 7/16" FILLER	
JACK STUDS: SINGLE EACH SIDE 2X4 #2SYP	
FIRE BLOCKING: 2X4 ON EDGE AT THE CEILING LINE	
INSULATION: R-13 FACED	
SHEATHING: NONE	
SIDING: 3/8" SMART PANEL	COLOR: SEE SHEET A-201
TRIM: 1X4 SMART PANEL	COLOR: SEE SHEET A-201
SKIRTING: SHIP LOOSE (6) 4X12 SHTS SMART PNL PAINTED TO MATCH BODY IF ORDERED	
IF SKIRTING IS ORDERED, 12"X12"VENTS TO BE SHIPPED WITH MATERIAL.	

INTERIOR WALLS:	
WALL HIEGHT: FULL HIEGHT	
STUDS 2X4 #2SYP 16" O.C.	
BOTTOM PLATE: SINGLE 2X4 #3SYP	
TOP PLATES: DOUBLE 2X4 #3SYP	
FIRE BLOCKS: 2X4 ON EDGE AT CEILING LINE	
COVERING: 5/8" FIRE-X VCC COLOR: HAMTOM GRAY	
5/8" GREEN BOARD AT RESTROOM COVERED WITH FRP	
TRIM: STANDARD VCG BATTENS	
FRP: FULL HIEGHT AT RESTROOM	
INSULATION: R-13 UNFACED THROUGHOUT.	
MISC:	

WINDOWS:	
SIZE/TYPE: (3) 24"X52" V.S. BRONZE/CLEAR LOW E GLASS, SCREW ATTACHED	
BRAND:	HR
COVERING: (3)ALUMINUM MINI-BLINDS	COLOR: GRAY
MISC:	N/A

DOORS:	
EXTERIOR:	(1) 36"X80" 18GA STEEL W/ 5"X20" PENCIL WINDOW (TEMP)
EXTERIOR HARDWARE:	
	(1) DEADBOLT (SCHLAGE) B660 BD x 26D W/IC CONSTR. CORE
	(1) 9305BC x AL NORTON CLOSURER
	(1) HOLLOW METAL. FRAME
	(2) PULL PLATES ROCKWOOD #107 x 70C X US28
	(1) PEMCO THRESHOLD 170A-36
	(1) PEMKO SWEEP 315CN-36
	(1) SET PEMKO WEATHERSTRIP 303AV-3070
INTERIOR:	(2) 36"X80" MOHAWK SOLID CORE DOORS 1R W/ 5X20 PENCIL WINDOW, 1L W/O
	(1) 24"X80" MOHAWK SOLID CORE DOOR
	(2) 3680 REDIFRAMES 478 BROWN 20GA
	(1) 2468 REDIFRAME 478 BROWN 20GA
INTERIOR HARDWARE: LEVER HANDLES ON ALL	
	(1) HEAVY DUTY PRIVACY ND40S X RHODES x 26D (SCHLAGE) RESTROOM
	(2) HEAVY DUTY ENTRY ND53BD X RHODES x 26D (SCHLAGE) OFFICE-CLOSET
	W/ IC CONSTRUCTION CORE

ROOF:	
RAFTER:	2X8 #2SYP 16" O.C.
RIM:	SINGLE 2X8 #2SYP
SHEATHING:	7/16" FR DECK
BOTTOM RAFTER SHEATHING:	5/8" FIRE-X SHEETROCK
COVERING:	.045 EPDM COLOR: BLACK
ROOF PITCH:	.25/12 TRANSVERSE
CEILING:	8'-8" HEIGHT. 2X4 ARMSTRONG RADAR
INSULATION:	R-22 FACED
PLENUM:	AREA ABOVE CEILING GRID TO BE A PLENUM RETURN.
VENTS: N/A	

ELECTRICAL:	
SERVICE:	115/230V SINGLE PHASE
LOAD CENTER:	(1) 100 AMP, INT MOUNT LOAD CNT. WITH SURGE SUPPRESSION BY INTERMATIC
ENTRANCE:	2" NIPPLE DOWN METAL
WIRING:	MC CABLE W/#12 (#10 AT HVAC)
LIGHTS:	(5) 48" T-8 (4) TUBE 32WATT FLOURESCENT TROFFERS.
	(1) LPC PHOTO CELL EXTERIOR LIGHT
	(1) 24" T-8 U SHAPE 32 WATT FLOURESENT TROFFER IN RESTROOM
FANS:	(1) 90 CFM EXHAUST IN BATHROOM VENT THRU ROOF NUTONE 671R
SURGE PROTECT:	(1) INTERMATIC WIRED INTO SERVICE PANEL.
EXIT/EMERG. LIGHT:	(1) EXIT/EMERGENY LIGHT BATTERY BACK UP.
RECIEPTS	(5) STD. 120V DUPLEX RECEP (3) SURGE BLOCK DUPLEX RECT.
	(3) GFCI 120V STD. DUPLEX RECEPTACLES
	(1) W.P. EXT. GFCI 120V RECEPTACLE
	(1) DEDICATED (4)120V SURGE RECEPTACLE (TELECOM BOX)
SWITCHES	(3) OCCUPANCY SENSORS(INFRARED ULTRASONIC)-LEVITON
J-BOXES:	ALL PLATES TO BE IVORY
ALARM:	N/A
MISC:	GROUNDING ON SITE TO BE PER NEC 2002, 250-96

PLUMBING:	
WATER SUPPLY:	TYPE "L" COPPER
WASTE:	PVC SCHEDULE 40
WATER HEATER:	(1) EeMAX SP55 SUPPLY TO BOTH SINKS
WATER CLOSET:	(1) HANDICAP FLUSH VALVE ELONGATED L/HANDLE
LAVITORY:	HANDICAP WALL HUNG, COVER UNDERNEATH HANDLES
BAR SINK:	(1) STAINLESS STEEL COUNTER LAV, DUAL LEVER FAUCET.
ACCESSORIES:	36" AND 42" GRAB BARS, TOLIET PAPER HOLDER.
NOTE:	ALL FIXTURE MOUNTING PER TAS 1994

HVAC:	
HVAC:	(1) 2 TON WITH 5KW HEAT STRIP W/ DISCONNECTS.
	BARD COLOR: TAN
THERMOSTAT:	(1) PROGRAMABLE
DUCTS:	MANVILLE DUCT BOARD, FLEX TO GRILLS
SUPPLY REGISTERS:	24X24 W/ ADJUSTABLE DIFFUSERS
RETURN REGISTERS:	24X24 , ABOVE CEILING PLENUM WITH PLENUM WALL CUT OUTS
MISC:	FRESH AIR MAKEUP IS PROVIDED THRU MANUAL DAMPER IN HVAC
	ECONOMIZER IS INCLUDED IN THE UNIT FOR ENGERY CONSERVATION
DISCONNECT:	EXTERIOR 30AMP WITHIN 6' OF GROUND.

FURNITURE OR MISC:	
24" BASE CABINET, WITH ADA TOE KICK AND THREE DRAWERS.	
24" AND 42" WALL HUNG CABINETS W/SHELVES	
66" OF COUNTER TOP	
24'X48" MIRROR AT BATHROOM	
FIRE EXTINGUISHER CABINET (IN WALL) W/ 5LB EXTINGUISHER	

TELECOM:	
WIRE: TELEPHONE: CAT 5E PLENUM	COLOR: WHITE
LAN: CAT 6 PLENUM	COLOR: BLUE
JACKS: TELEPHONE: R-11 (IVORY)	
LAN: CAT6 (IVORY)	
J-BOXES: WIRED FOR (1)DATA, (1)VOICE	
VOICE/DATA HOUSING: 28" WITH LOCKING HINGE COVER	
MODULES:	
	(1) LEVINGTON (4 PORT ROUTER)
	(1) LEVINGTON (6 PHONE & 6 DATA)
PUNCH DOWN: DATA TO BE PUNCHED AS T-568A	
DEMARC: MOUNTED AT HITCH END, WIRED TO CLOSET.	
CAT6, CAT5E AND RJ-6 RUNS TO CLOSET	
PLATES: IVORY 4-PORT, (2) COVERED	
OUTLET: DEDICATED LINE TO LEVINGTON SURGE OUTLET	
LOCATED IN THE HOUSING	

TRANSPORTATION:		
7/16	ROOF DECK	0.0416667
2X8	ROOF RAFTER	0.6041667
5/8 GYP	UNDERSIDE RAFTER	0.0520833
10'-8"	TALLEST WALL	10.666667
1/4"	FLOOR COVER	0.020833
3/4"	FLOOR DECK	0.0625
2X8	FLOOR JOIST	0.6041667
2'-8"	TO ROAD APPROX	2.625
		14.677083 FT
TOTAL		14'-8 1/4" APPROX.
WEIGHT APPROX.		12375 LBS

NOTE THAT ALL SPECIFIC NAILING PATTERNS SHOWN ON SF DRAWINGS ARE TO OVERRIDE THE DESIGN MANUAL PATTERNS.

DRAWING INDEX:	
G-001	= COVER
A-101	= FLOOR PLAN
A-201	= EXTERIOR ELEVATIONS
A-202	= INTERIOR ELEVATIONS
A-301	= SECTIONS
A-601	= ADA(TAS)
E-101	= ELECTRICAL PLAN
M-101	= MECHANICAL(HVAC) PLAN
P-101	= PLUMBING PLAN
P-601	= NOT USED
SF-101	= FLOOR FRAMING PLAN
SF-102	= FLOOR DECKING/WALL LAYOUT PLAN
SF-103	= ROOF FRAMING PLAN
SF-201	= WALL FRAMING PLAN
SF-202	= WALL FRAMING PLAN
S-101	= FOUNDATION PLAN
S-102	= NOT USED
S-501	= NOT USED
T-101	= TELECOM PLAN

JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:	
				REW	NORTEX MODULAR SPACE	STOCK 1430 COVER-"J" SERIES	
				DATE:	SCALE:	DWG#	SHEET:
				02/19/07	N/A	1430STK	G-001




**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704

AREA SCHEDULE							
DESIGNATION	DESCRIPTION	FLOOR AREA	CUBIC AREA	FLOOR	WALL	CEILING	BASE
100	OFFICE	121	1051	CARPET	5⁄8" VINYL COVERED GYPSUM TYPE X	2'X4' LAY IN	4" RUBBER BASE
101	BATHROOM	42	364	TILE	FRP OVER 5⁄8" GYPSUM TYPE X	2'X4' LAY IN	4" RUBBER BASE
102	WORK AREAS AND SINK AREA	183	1592	TILE	5⁄8" VINYL COVERED GYPSUM TYPE X	2'X4' LAY IN	4" RUBBER BASE
103	TELECOM	5	43	TILE	5⁄8" VINYL COVERED GYPSUM TYPE X	2'X4' LAY IN	4" RUBBER BASE

WINDOW SCHEDULE			
DESIGNATION	DESCRIPTION	RD	QTY
W1	2044 ALUMINUM BRONZE FRAME, DOUBLE INSULATED LOW E GALSS W/ ALUMINUM MINI BLINDS	24½" X 52½"	3

DOOR SCHEDULE					
DESIGNATION	SIZE	DOOR MATERIAL	FRAME	RD	QTY
D1	3068L	STEEL W/ PENCIL VISION	STEEL	40½" X 82½"	1
D2	3068R	MOHAWK SOLID CORE W/ VISION GLASS	REDIFRAME	37" X 81"	1
D3	3068L	MOHAWK SOLID CORE	REDIFRAME	37" X 81"	1
D4	2068R	MOHAWK SOLID CORE	REDIFRAME	25" X 81"	1




FLOOR PLAN

JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611


LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 FLOOR PLAN-"J" SERIES
				DATE:	SCALE:	DWG#
				04/27/07	3/16" = 1'-0"	1430
						SHEET:
						A-101




**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704




BACK ELEVATION



BACK END ELEVATION



FRONT ELEVATION




HITCH END ELEVATION

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 ELEVATIONS-"J" SERIES
				DATE:	SCALE:	DWG#
				04/26/07	3/16" = 1'-0"	1430STK




JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704



555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704



SECTION VIEW

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 SECTION-"J" SERIES
				DATE:	SCALE:	DWG#
				04/27/07	3/8" = 1'-0"	1430STK
						SHEET:
						A-301




JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611


**NORTEX MODULAR SPACE**

555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704


ADA DETAILS




WATER CLOSET  
SIDE VIEW



WATER CLOSET  
FRONT VIEW



LAV CLEARANCES



CLEAR FLOOR SPACE  
AT LAVATORIES

UNIT PARTICULARS:  
GRAB BARS 35" AFF  
SINK IN BATHRRROM 33" AFF  
MIRROR 39" AFF TO BOTTOM  
BATHROOM SINK, 16" FROM WALL TO CENTER.

LTR	REVISION	BY	DATE	DRAWN BY:
				REW
				DATE: 04/27/07

PROJECT:	NORTEX MODULAR SPACE
SCALE:	N/A

TITLE:	STOCK 1430 ADA-"J" SERIES
DWG#	1430STK

SHEET:	A-601
--------	-------



JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704



MECHANICAL SCHEDULE		
DESIGNATION	DESCRIPTION	COMMENTS
SA1	2X2 SUPPLY AIR REGISTER	ADJUSTABLE
SA2	12X12 SUPPLY GRILL	NONE
RA1	2X2 RETURN AIR REGISTER	NONE
T	THERMOSTAT	PROGRAMMABLE
2½ TON W/10KW	BARD MODELWA42	W/ECONOMIZER
EX1	90 CFM EXHAUST FAN	THRU ROOF

Unit 1430

# AIR EXCHANGES


Entire Bulding Quick Calcuation				
L '	W '	H '		Volume
30	13.75	8.67		3576.375
5				715.275

MIN. CFM

Actual Room Calculations						
Room	L '	W '	H '	SF	Volume	% of bldg
100	9.33	13	8.67	121.29	1051.58	34.96%
101	6	7	8.67	42	364.14	12.11%
102	varies	13	8.67	183	1592.00	52.93%
103	0	0	0	0	0.00	0.00%
104	0	0	9	0	0.00	0.00%
105	0	0	9	0	0.00	0.00%
106	0	0	9	0	0.00	0.00%
107	0	0	9	0	0.00	0.00%
108	0	0	9	0	0.00	0.00%
108	0	0	9	0	0.00	0.00%
5 AIR CHANGES=					3007.72	100%
					601.54	CFM

AC	CFM	FPM	RECT W	RECT W	ROUND DUCT
2 TON	800	600	20	8	16

TELCOM BOX



- NOTES:
1. PLENUM CAVITY ABOVE LAY IN CEILING.
  2. PLENUM WALL TO HAVE OPENINGS CUT AND GYPED TO ACHIVE 30X16 RETURN AREA.
  3. OFFICE WALLS AND 2X6 WALL TO HAVE OPENING FOR DUCT TO PASS THRU FABRICATED INTO FRAMING.
  4. FLEX DUCTS NOT TO BE CUT INTO MAIN DUCT LESS THAN 12" FROM A TRANSITION.

MECHANICAL PLAN


LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 MECHANICAL PLAN-"J" SERIES
				DATE:	SCALE:	DWG#
				05/01/07	3/16" = 1'-0"	1430STK



JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704






ALL SUPPLY LINES ARE 1/2"  
EXCEPT AS NOTED  
ALL STUB-OUTS ARE 3/8"  
EXCEPT AS NOTED


NOTE: ALL SUPPLY LINES OVER  
3/4" IN SIZE SHALL BE COPPER

SUPPLY RISER



DWV RISER

CONNECTING HARNESS WORK AND UNDERGROUND TO BE BY OTHERS IN THE FIELD.



36" AND 42" GRAB BARS  
ARE 35" AFF TO CENTER.  
BATHROOM SINK TO BE  
MOUNTED 31 1/2" AFF TO  
BRACKET TOP.  
SEE SHEET A-601 FOR  
OTHER DETAILS.


LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 PLUMBING PLAN-"J" SERIES
				DATE:	SCALE:	DWG#
				05/03/07	3/16" = 1'-0"	1430STK
						SHEET: P-101



JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**

555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704



FLOOR JOIST PLAN

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 FLOOR JOIST PLAN-"J" SERIES
				DATE:	SCALE:	DWG#
				05/03/07	3/16" = 1'-0"	1430STK


SHEET: SF-101



JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704


SHEARWALL SCHEDULE					
MARK	MATERIAL	FASTEN STUDS TO SIDING	FASTEN BOTTOM PLATE TO DECK	FASTEN TOP PLATE TO RAFTERS	FASTEN END TO SIDEWALLS
SW1	7/16" SMARTPANEL ONESIDE 5/8" VCG OTHER SIDE	NAIL 3/8" SMART PANEL AT 5"OC EDGE/10" OC FILED WITH .09 X 2-3/16" NAIL. ADHESIVE VCG ON INTERIOR	.131 X 3" NAILS 16" O.C.	.131 X 3" NAILS 16" O.C.	.131 X 3" NAILS 16" O.C.
SW2	5/8" VCG EACH SIDE	ADHESIVE EACH SIDE	.131 X 3" NAILS 16" O.C.	.131 X 3" NAILS 16" O.C.	.131 X 3" NAILS 16" O.C.




FLOOR DECK / WALL LAYOUT PLAN

- NOTES:
- ADHESIVE TO BE USED ON DECKING.
  - EDGES ARE UNBLOCKED.
  - SCREW FLOOR 6"O.C. EDGES, 12" FIELD WITH 2 1/4" SCREWS.
  - ALL WALLS 2X4 EXCEPT BATHROOM WET WALL, TO BE 2X6.

\* DENOTES SIDE TO BE  
PREGYPED  
# DENOTES TO FINISH

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:	 <b>NORTEX MODULAR SPACE</b> 555 JUBILEE LANE LEWISVILLE, TX 75056 PHONE: 972-492-4040 FAX: 972-492-2704
				REW	NORTEX MODULAR SPACE	STOCK 1430 FLOOR DECK PLAN-"J" SERIES	
				DATE:	SCALE:	DWG#	SHEET:
				02/19/07	3/16" = 1'-0"	1430STK	SF-102



ROOF JOIST PLAN


- NOTES:
- 1. FILL CAVITY WITH R19.
  - 2. BOTTOM OF JOIST TO BE 5/8" GYPSUM.
  - 3. ROOF DECK TO BE FR DECK PANEL.
  - 4. ROOF DECK NAILING TO BE 4" OC EDGE & 8" OC IN FIELD SCREW ATTACHED WITH 2 1/4" SCREWS.
  - 5. ROOF IS BUILT IN 30' HALFS.

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:		
				REW	NORTEX MODULAR SPACE	STOCK 1430 ROOF JOIST PLAN-"J" SERIES		
				DATE:	SCALE:	DWG#	SHEET:	
				04/30/07	3/16" = 1'-0"	1430STK	SF-103	




JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704



2 SIDEWALL



1 SIDEWALL










NOTES:  
ALL WINDOWS AND DOOR  
OPENINGS TO HAVE DOUBLE KING  
STUDS AT EXTERIOR WALLS.  
ALL HEADERS ARE (2)-2X6'S.  
ALL WALLS EXCEPT HITCH END  
REQUIRE BLOCKING AT 8'-8\"/>

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 WALL FRAMING-"J" SERIES
				DATE:	SCALE:	DWG#
				05/02/07	3/16" = 1'-0"	1430STK



**JOE STEEDE, P.E.**  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704





NOTE: ALL SUPPLY AND RETURN OPENINGS TO BE GYPED INSIDE, IE: NO EXPOSED WOOD.

JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 WALL FRAMING-"J" SERIES
				DATE:	SCALE:	DWG#
				05/02/07	3/16" = 1'-0"	1430STK
						SHEET: SF-202



**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704




- NOTES:
1. SOIL ASSUMED AT 2500PSI
  2. PAD SPACING SHOWN IS FOR 50PSF FLOOR LOADS. SPACING OF PADS CHANGES TO 4'-4" O.C. FOR 100PSF FLOOR LOADS.
  3. ANY ADDITIONAL STRAPS REQUIRED BY LOCAL AUTHORITIES WILL BE FRAME STRAPS.

TYPICAL OVER ROOF TIE (5) REQ'D LOCATE AS TO NOT INTERFERE WITH DOORS OR WINDOWS.


JOE STEEDE, P.E.  
13999 GOLDMARK, SUITE 374  
DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**  
555 JUBILEE LANE  
LEWISVILLE, TX 75056  
PHONE: 972-492-4040  
FAX: 972-492-2704


LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:
				REW	NORTEX MODULAR SPACE	STOCK 1430 FOUNDATION PLAN-"J" SERIES
				DATE:	SCALE:	DWG#
				05/02/07	3/16" = 1'-0"	1430STK
						SHEET: S-101



NTS



NTS



NOTES:  
 DATA CABLE TO BE  
 BLUE CAT 6  
 UNSHIELDED, PLENUM  
 RATED. VOICE  
 CABLE TO BE WHITE  
 CAT 5E UNSHIELDED,  
 PLENUM RATED.  
 CABLE TO BE RG-6  
 PLENUM RATED.  
 ALL WALL  
 PENETRATIONS TO  
 BE FIRE CAULKED  
 TO MAINTAIN  
 PLENUM INTEGRITY.

JOE STEEDE, P.E.  
 13999 GOLDMARK, SUITE 374  
 DALLAS, TX 75250 PHONE 972-238-1611

**NORTEX MODULAR SPACE**

555 JUBILEE LANE  
 LEWISVILLE, TX 75056  
 PHONE: 972-492-4040  
 FAX: 972-492-2704

LTR	REVISION	BY	DATE	DRAWN BY:	PROJECT:	TITLE:	DWG#	SHEET:
				REW	NORTEX MODULAR SPACE	STOCK 1430 TELECOM PLAN-"J" SERIES	1430STK	T-101
				DATE:	SCALE:			
				05/02/07	3/16" = 1'-0"			